SafetyWithAthar Remote HSE Documentation
Document Title: Civil Excavation & Underground Utility JSA / JHA
Category: JSA / JHA | Status: Public-source demo sample (Rev. 0 For review only)

Summary: Step-by-step Job Safety Analysis breaking down utility scanning, trench shoring, spoil

[Page 1] Job Safety Analysis (JSA / JHA) Deep Trenching & Utilities (SWA-JSA-CIV-014)
Job Step Sequence | Potential Hazards | Preventive Controls | Action By
---
* Step 1: Underground Service Scan Strike on energized HV cable or pressurized pipe
  [As-built drawing check + calibrated CAT4 scan + mark route] -> Surveyor / HSE [HOLD] (PTW Gat
* Step 2: Trial Pit Hand Digging Mechanical bucket contact with buried conduit
  [Insulated hand tools within 500mm of marked service line] -> Civil Foreman (Verified)
* Step 3: Trench Battering & Shoring Sidewall cave-in / worker entrapment (>1.2m depth)
  [Install hydraulic trench box or 45 benching + 1m spoil clearance] -> Site Engineer (Engineer
* Step 4: Access & Gas Monitoring Oxygen deficiency / H2S accumulation in deep cut
  [Multi-gas detector pre-entry check + secured ladder every 7.5m] -> Authorized Gas Tester (Log
Note: Public-source demo sample Rev. 0 For review only. Ready for site crew briefing.

Prepared by Muhammad Athar SafetyWithAthar (https://athar-beep.github.io/safetywithathar/)