SafetyWithAthar Remote HSE Documentation
Document Title: Activity-Based Risk Assessment Structural Work Pack
Category: Risk Assessment | Status: Public-source demo sample (Rev. 0 For review only)

Summary: 5 5 initial & residual risk matrix covering 39 pages of civil/structural activities, hi

[Page 1] Activity-Based Risk Assessment Matrix (5 5 Initial Residual) (SWA-HSE-RA-001)
Activity Step | Hazard & Consequence | Init Risk | Controls & Hold Points
---
* 01. Sub-structure Excavation Underground live cable strike / trench collapse
  [20 (High)] -> PTW + CAT scan + trial pit hand-dig [HOLD POINT] (Res: 4 (Low))
* 02. Mobile Crane Rigging Load drop / outrigger ground bearing failure
  [16 (High)] -> 3rd-party lift plan, spreader mats, anemometer <20 kt (Res: 4 (Low))
* 03. Steel Column Erection Fall from height / Pinch point during bolt-up
  [15 (High)] -> MEWP rescue plan, 100% twin-lanyard tie-off, taglines (Res: 3 (Low))
* 04. Grouting & Chemical Curing Dermal/respiratory exposure to epoxy grouts
  [10 (Med)] -> COSHH assessment + SDS on site + nitrile/respirator PPE (Res: 2 (Low))
Note: Public-source demo sample Rev. 0 For review only. Unconfirmed site values marked [HOLD

[Page 2] 5 5 Risk Evaluation Key & Client HSE Authority Sign-Off (SWA-HSE-RA-001)
Control Hierarchy Tier | Verification Method | Owner Role | Gate Status
---
* 1 3. Elimination & Engineering Temporary shoring design & certified lifting gear register
  [Package Engineer] -> [HOLD POINT 01] (Mandatory)
* 4. Administrative & PTW Pre-shift TBT sign-off & exclusion zone barricading
  [Site HSE Officer] -> Shift Inspection (Active)
* 5. PPE & Emergency Rescue Full body harness EN 361 + tripod retrieval standby
  [Rescue Team Lead] -> Verified Pre-Start (Checked)
Note: Drafted remotely by Muhammad Athar (SafetyWithAthar) for review and approval by site HSE a

Prepared by Muhammad Athar SafetyWithAthar (https://athar-beep.github.io/safetywithathar/)