Method Statement (MOS) - Critical & Routine Lifting Operations

Sections: 1. Scope - 2. Plant & Gear Certs - 3. Operational Sequence - 4. Hold Points - 5. Emergency Plan

---

4.1 Crane Positioning & Mats
Mandatory Technical Control: Verify ground compaction report & 100% outrigger beam extension
Hold Point / Limit: [HOLD POINT] Prior to boom raise
Sign-Off Role: Lifting Supervisor
Gate 01

4.2 Rigging & Color Code Check
Mandatory Technical Control: Inspect shackles, web slings & SWL tags against valid 6-month 3rd-party cert
Hold Point / Limit: SWL > 125% load weight
Sign-Off Role: Certified Rigger
Gate 02

4.3 Wind & Weather Monitoring
Mandatory Technical Control: Continuous digital anemometer reading at boom tip elevation
Hold Point / Limit: Cease lift if wind >= 20 knots
Sign-Off Role: Crane Operator / HSE
Stop Work

4.4 Exclusion Zone & Taglines
Mandatory Technical Control: Hard physical barriers around slewing radius; twin non-conductive taglines
Hold Point / Limit: Zero personnel under suspended load
Sign-Off Role: Appointed Banksman
Enforced

---

1. Scope & References

This statement covers the defined lifting scope only; variations require revision and re-approval.

Applicable Codes
Detail: LOLER / ASME B30 series / manufacturer manuals
Control / Requirement: Current revisions held by document control
Verification: Register

Scope Boundary
Detail: Loads, cranes and locations as listed in the lift plan
Control / Requirement: Out-of-scope lifts need a new plan
Verification: Plan

Reference Drawings
Detail: Plot plan + load charts [SITE INPUT REQUIRED]
Control / Requirement: Verified revision at workface
Verification: Doc control

Interfaces
Detail: SIMOPS with adjacent packages
Control / Requirement: Daily coordination meeting
Verification: Minutes

2. Roles & Responsibilities

Named, competent appointments for every lifting role - no informal substitution.

Appointed Person
Detail: Owns the lift plan and categorisation
Control / Requirement: Competency certificate on file
Verification: Appointment letter

Lift Supervisor
Detail: Controls the lift on the day
Control / Requirement: Briefs crew, can stop the lift
Verification: TBT record

Crane Operator
Detail: Operates within chart limits only
Control / Requirement: Licence + medical current
Verification: Cert check

Slinger / Signaller
Detail: Rigging and signals only
Control / Requirement: Certified, uses standard signals / radio
Verification: Cert check

3. Plant, Equipment & Certification

No equipment works without current third-party certification and pre-use checks.

Crane Certification
Detail: Third-party thorough examination current
Control / Requirement: Cert displayed + copy in lift pack
Verification: Register

Lifting Accessories
Detail: Slings, shackles, spreader beams colour-coded
Control / Requirement: Quarantine bin for defective gear
Verification: Gear register

Ground Assessment
Detail: Bearing capacity verified for outrigger loads
Control / Requirement: Mats/pads sized per calculation [HOLD POINT]
Verification: Calc sheet

Pre-Use Checks
Detail: Daily operator checklist before first lift
Control / Requirement: Defects = machine stood down
Verification: Checklist

4. Sequence of Operations - Rigging & Setup

Setup sequence is followed in order; shortcuts invalidate the lift plan.

Position Crane
Detail: Per plot plan, outriggers fully extended
Control / Requirement: Level within manufacturer tolerance
Verification: Supervisor check

Rig the Load
Detail: Sling angles - design minimum, CoG confirmed
Control / Requirement: Trial lift 100 mm to verify balance [HOLD POINT]
Verification: Trial record

Set Exclusion Zone
Detail: Hard barriers at swing + drop radius
Control / Requirement: Sentries posted at entry points
Verification: Walk-round

Comms Check
Detail: Radio channel + hand-signal backup agreed
Control / Requirement: All stations acknowledge
Verification: Log

5. Sequence of Operations - The Lift

One signaller controls the lift. Any person may call STOP.

Trial Lift
Detail: Raise 100 mm, hold, check balance + brakes
Control / Requirement: Abort and re-rig if load tilts
Verification: Supervisor

Travel / Slew
Detail: Slow movements, tag lines controlling rotation
Control / Requirement: Never over personnel - route pre-cleared
Verification: Sentries

Landing
Detail: Load landed on prepared bearers
Control / Requirement: Hands clear until load is stable
Verification: Supervisor

De-Rig
Detail: Slings removed only after load secured
Control / Requirement: Gear inspected before storage
Verification: Gear register

6. Critical Lift Criteria

Lifts meeting any criterion are planned as critical with enhanced controls.

> 75% of Chart Capacity
Detail: Utilisation calculated at worst radius
Control / Requirement: Critical lift plan + AP sign-off [HOLD POINT]
Verification: Plan

Tandem / Multi-Crane
Detail: Load share per crane calculated
Control / Requirement: Single lift director, rehearsed signals
Verification: Plan

Personnel Lifting
Detail: Only with certified man-basket + dedicated plan
Control / Requirement: Separate approval [HOLD POINT]
Verification: Permit

Blind Lift
Detail: Operator cannot see load or landing
Control / Requirement: Relay signallers + CCTV where fitted
Verification: Plan

7. Weather & Environmental Limits

Limits are hard stops, not guidance.

Wind
Detail: Stop at manufacturer limit or 20 kt default
Control / Requirement: Anemometer at jib height
Verification: Log

Lightning
Detail: 30-30 rule - stop, lower, stand clear
Control / Requirement: Resume 30 min after last thunder
Verification: Log

Visibility
Detail: Fog/darkness - lighting or postpone
Control / Requirement: Signaller visible at all times
Verification: Decision log

Ground After Rain
Detail: Re-verify bearing before resuming
Control / Requirement: Re-inspection recorded
Verification: Checklist

8. HSE Controls & PPE

Task PPE supplements - never substitutes - engineered controls.

PPE Matrix
Detail: Helmet, hi-vis, gloves (rigging), safety footwear
Control / Requirement: Harness only where MEWP/basket work applies
Verification: Issue record

Exclusion Enforcement
Detail: No entry under any circumstance during lift
Control / Requirement: Sentries empowered to stop
Verification: Briefing

Housekeeping
Detail: Rigging area kept clear of trip hazards
Control / Requirement: Daily tidy of laydown
Verification: Walk-round

Fatigue
Detail: Operator hours within site limits
Control / Requirement: No lift with fatigued operator
Verification: Roster

9. Quality - Inspection & Test Plan (Summary)

Hold and witness points agreed with the client inspector before work.

Material Receiving
Detail: Certs + visual inspection on delivery
Control / Requirement: Witness point
Verification: ITP sign

Pre-Lift Inspection
Detail: Crane + gear + ground verified
Control / Requirement: Hold point
Verification: ITP sign

Trial Lift
Detail: Balance and brake hold verified
Control / Requirement: Hold point
Verification: ITP sign

Final Acceptance
Detail: Load set and secured per drawing
Control / Requirement: Sign-off before de-rig crew leaves
Verification: ITP sign

10. Training & Competency Records

Copies held in the lift pack; originals with document control.

Operator Licence
Detail: Category-matched and in date
Control / Requirement: Checked weekly against register
Verification: Register

Rigger Certification
Detail: Level per national/company scheme
Control / Requirement: Colour-coded ID
Verification: Register

Medical Fitness
Detail: Fitness for role confirmed
Control / Requirement: Expiry tracked
Verification: Register

Induction & Briefing
Detail: Site induction + this statement briefed
Control / Requirement: Signed briefing sheet
Verification: File

11. Waste & Environmental Protection

Lifting operations protect ground and drains at setup and breakdown.

Hydraulic Leaks
Detail: Drip trays under parked plant
Control / Requirement: Spill kit at crane pad
Verification: Inspection

Timber & Packing Waste
Detail: Segregated at source
Control / Requirement: Licensed removal route
Verification: Waste log

Noise
Detail: Plant idling minimised near receptors
Control / Requirement: Working hours respected
Verification: Log

Fuel Storage
Detail: Bunded, away from drains
Control / Requirement: Refuelling procedure followed
Verification: Checklist

12. Management of Change

Any change to load, crane, ground, or sequence stops the job until re-planned.

Change Trigger
Detail: Different load weight/CoG or crane position
Control / Requirement: STOP - notify Appointed Person
Verification: MOC form

Re-Planning
Detail: Plan revised + re-briefed
Control / Requirement: New revision number issued
Verification: Doc control

Field Copies
Detail: Superseded plans withdrawn same shift
Control / Requirement: Permit office check
Verification: Register

Crew Re-Brief
Detail: Whole crew signs new revision
Control / Requirement: No signature = no participation
Verification: Briefing sheet

13. Records & Handover Pack

The completed lift pack is handed to document control at package close-out.

Lift Plans (As-Used)
Detail: Signed, with any field amendments marked
Control / Requirement: Filed per package
Verification: Pack index

Checklists & Permits
Detail: Daily checks + permits complete
Control / Requirement: No gaps unexplained
Verification: Pack index

Incident / Near-Miss Reports
Detail: All events logged, actions closed
Control / Requirement: Lessons briefed to next package
Verification: Register

Certification Copies
Detail: Crane + gear + personnel
Control / Requirement: Valid at date of each lift
Verification: Pack index

14. Interfaces With Other Contractors

Shared work areas are coordinated daily; assumptions are treated as hazards.

SIMOPS Meeting
Detail: Daily, all package supervisors
Control / Requirement: Conflicts resolved before permits issue
Verification: Minutes

Shared Crane Use
Detail: Booking system with priority rules
Control / Requirement: No double-booking of radius zones
Verification: Booking log

Overhead Conflicts
Detail: Adjacent cranes anti-collision briefing
Control / Requirement: Slew limits set where fitted
Verification: Plan

Ground Sharing
Detail: Outrigger zones kept clear by all trades
Control / Requirement: Barriers respected site-wide
Verification: Walk-round

15. Continuous Improvement

Each completed lift improves the next plan.

Post-Lift Review
Detail: Crew debrief after critical lifts
Control / Requirement: Notes filed with plan
Verification: Review note

Near-Miss Trending
Detail: Monthly review of lifting near-misses
Control / Requirement: Actions tracked to close
Verification: Register

Plan Library
Detail: Proven plans indexed for reuse (with re-validation)
Control / Requirement: Re-validation mandatory per site
Verification: Library

Audit
Detail: Quarterly lifting audit by HSE
Control / Requirement: Findings to management review
Verification: Audit report

Emergency Response Summary

Site emergency arrangements to be confirmed against the actual project emergency plan before work starts.

Injury / Collapse
Immediate Action: Stop work, first aid, call site emergency number
Equipment: First aid station + stretcher
Notification: Supervisor - HSE Officer

Fire
Immediate Action: Raise alarm, attack only if trained and safe
Equipment: Extinguishers at work point
Notification: Control room / fire team

Load Incident
Immediate Action: Cordon area, do not re-rig until inspected
Equipment: Barriers + lifting register
Notification: Lifting supervisor - HSE

Adverse Weather
Immediate Action: Stand down lifting/height work at limits
Equipment: Anemometer + lightning rule
Notification: Site management broadcast

Review, Approval & Revision Record

This document is a professional draft. Field use requires review and formal approval by the client/site HSE authority.

Prepared By
Name / Organisation: SafetyWithAthar (remote)
Responsibility: Draft preparation from supplied work-pack inputs
Status: Rev. 0 issued

Reviewed By
Name / Organisation: [SITE INPUT REQUIRED]
Responsibility: Site HSE review against actual conditions
Status: [HOLD POINT]

Approved By
Name / Organisation: [SITE INPUT REQUIRED]
Responsibility: Client / site HSE authority approval
Status: [HOLD POINT]

Revision History
Name / Organisation: Rev. 0 - first issue for review
Responsibility: Superseded revisions withdrawn from field use
Status: Controlled